

Beaver Crossing Southeast

BRO-7080(55); CN 13521



Project Location

Identified as **Beaver Crossing Southeast**, the proposed project would reconstruct the bridge on the West Fork of the Big Blue River (406th Road) southeast of Beaver Crossing in Seward County. The project would begin approximately 0.25 miles south of the Pioneers Road intersection. Construction may begin and/or end approximately 500 feet on either end of the bridge to accommodate tying into the existing surface.



Improvements

The proposed improvements on this project would consist of replacing the bridge on Big Blue River (Structure No. C008001115) with a new bridge that would be replaced with a 150-foot, 3-span continuous concrete slab bridge and a 28-foot clear width roadway and adding new guardrails. Grading beyond the hinge point will be required at spot locations for the entire length of this project.



Purpose & Need

The purpose of the project is to improve the reliability of the transportation system and perpetuate the mobility of the traveling public. The need for the project is based on the bridge's current condition.



Project Impacts

The proposed project would require the acquisition of additional property rights, which could include new right-of-way (ROW), control of access (CA), permanent easements (PE), and/or temporary easements (TE). If your property is impacted by this project, you will be contacted by a representative once the design footprint has been established. Access to adjacent properties would be maintained during construction but may be limited at times due to phasing requirements.

Impacts to Big Blue River are anticipated. Wetland and channel mitigation is not anticipated. No impacts are anticipated to any parks, trails, or historic properties.

The project would be constructed under full closure. 406th Road is currently closed to traffic and the roadway will remain closed during construction.



Anticipated Cost

The anticipated cost of the project is approximately \$2.24 million with funding derived from federal sources.



Anticipated Schedule

Construction could begin as early as spring 2028 and be completed by fall 2028.



For additional information, contact:

Jon Regnier
Seward County Highway Superintendent
529 Seward Street - Room 206
Seward, NE 68434
(402) 643-3170
jregnier@sewardcountyne.gov

Project Website



sewardcountyne.gov/roads-and-bridges

The environmental review, consultation, and other actions required by applicable Federal environmental laws for this project are being, or have been, carried out by NDOT pursuant to 23 U.S.C. 327 and a Memorandum of Understanding dated February 23, 2026 and executed by FHWA and NDOT.

Beaver Crossing Southeast Location Map

BRO-7080(55); CN 13521

